Bruhat Bangalore Mahanagara Palike
Excecutive Engineer Yelahanka Project Division

Name of Work: Providing Solid Waste Management works in ward no 07

Agency:-M/s KRIDL

Schedule - B

Sl No	Quantity	Description of Item	Unit	Approved Rates of M/s KRIDL	
				In Figures	In Words
1	5.00	Supplying ,installation ,Commissioning and Testing CP PLUS 2 MP PTZ, 1/2.8" 2MP Exmor R CMOS Image sensor Max. 50/60fps@1080P, 25/30/50/60fps@720P,Powerful 25x Optical and 16x Digital zoom WDR(120dB), 3D DNR, Day/Night(ICR), BLC, HLC Up to 300 presets, 8 auto scan, 8 tour, 5 pattern, 8 auto pan IR Range of 150 Mtr. , IP66, Support PoE Plus inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	82962.00	Rupees Eighty Two Thousand Nine Hundred Sixty Two Only
2	45.00	Supplying ,installation ,Commissioning and Testing CP PLUS 3 MP , 50 meters ip bullet camera,1/3" 3MP PS CMOS Image Sensor,Max 25fps@3MP, 25/30fps@1080P,H.264, H.264H, H.264B , MJPEG dual-codec encoding,DWDR, Day/Night(ICR), 3DNR, ROI, AWB, AGC, BLC, HLC,3.6mm fixed lens (6mm optional),IR Range of 50 Mtrs, IP67, SD Card, PoE,Mobile Software: iCMOB, gCMOB,CMS Software: KVMS Pro, vOptimus Pro inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	23160.00	Rupees Twenty Three Thousand One Hundred Sixty Only
3	2.00	Supplying ,installation ,Commissioning and Testing CP PLUS 32 Ch. H.265 4K Network Video Recorder Up to 32 channel IP camera input H.265/H.264 dual codec decoding Up to 8Mp resolution preview and playback Max 200Mbps incoming bandwidth Support 4 SATA HDDs up to 24TB, 2 USB(1 USB3.0) HDMI / VGA simultaneous video output Support Multi-brand network cameras ONVIF Version 2.4 conformance Mobile Software: iCMOB, gCMOB inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	66892.00	Rupees Sixty Six Thousand Eight Hundred Ninety Two Only
4	1.00	Supplying, installation ,Commissioning and Testing Netgear ReadyNAS 4-Bay Diskless Network Attached Storage for Personal Cloud by Netgear inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	257420.00	Rupees Two Lakh(s) Fifty Seven Thousand Four Hundred Twenty Only
5	6.00	Providing and Supplying NAS hard disk drives 6 TB inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	22850.00	Rupees Twenty Two Thousand Eight Hundred Fifty Only

Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Project Division
Yelahanka Zone

Sl No	Quantity	Description of Item	Unit	Approved Rates of M/s KRIDL	
				In Figures	In Words
6	12.00	Supplying, installation, Commissioning and Testing D-Link 8-Port Gigabit Switch With 2 Combo SFP Ports inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	28500.00	Rupees Twenty Eight Thousand Five Hundred Only
7	2.00	Providing and Supplying CAT6 OUT Door 305 mtr Cable Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	64250.00	Rupees Sixty Four Thousand Two Hundred Fifty Only
8	3.00	Providing and Fixing Media converter Giga Dlink inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	12200.00	Rupees Twelve Thousand Two Hundred Only
9	1960.00	Providing and Fixing OFC cable single mode 6 core inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	165.00	Rupees One Hundred Sixty Five Only
10	16.00	Providing Cctv MS poles with camera fixing brackets, 5 to 6 mtr height Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	22500.00	Rupees Twenty Two Thousand Five Hundred Only
11	13.00	Providing and Fixing MS Boxes for Poles with rust proof powder coating Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	9500.00	Rupees Nine Thousand Five Hundred Only
12	15.00	Providing and Fixing Electrical work for boxes for power supply, fixing PVC Boards with three pin socktes and switches with protection MCB and cabling to street light electrical poles as per the direction of Engineer in Charge	Nos	8500.00	Rupees Eight Thousand Five Hundred Only
13	12.00	Providing Internet charges connecting CCTV with IP Based for one month	Nos	3500.00	Rupees Three Thousand Five Hundred Only
14	24.00	Providing and Fixing SFP-LX-SM GIGA MODULE Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	6500.00	Rupees Six Thousand Five Hundred Only
15	20.00	Providing and Fixing Fibre Optic PATCH Chords Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	2200.00	Rupees Two Thousand Two Hundred Only
16	10.00	Erecting of pole .The pole shall be erected n cement concrete work(1:2:4) including earthwork excavation and refilling of planting depth of the pole to the ground level and the copping CC shall be upto 0.6m above ground level as per IS 2713-7.1 Erection of lightduty pole on footpath a) 7.5m as per IS 410 Sp 5 charges as per the direction of Engineer in Charge	Nos	6400.00	Rupees Six Thousand Four Hundred Only
17	2.00	Providing and Fixing HDMI Cables 10 Mtrs inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	6500.00	Rupees Six Thousand Five Hundred Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Contractor

Executive Engineer
Project Division
Yelahanka Zone

No	Quantity	Description of Item	Unit	Approved Rates of M/s KRIDL	
				In Figures	In Words
18	2.00	Supplying ,installation ,Commissioning and Testing of 43'' LED TV – Reputed make Sony/Samsung/LG inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	45000.00	Rupees Forty Five Thousand Only
19	8.00	Supplying ,installation ,Commissioning and Testing Patch cords CAT6 2 Mtr Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	1200.00	Rupees One Thousand Two Hundred Only

18/1/19

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010